



CE
ISO9001



Terminal



Operating voltage

THREE PHASE SOLID STATE RELAY 60AA

TECHNICAL DETAILS



Mode	TSR-60AA
Control voltage	70-280 VAC
Maximum input current	40 mA
Switch-on voltage	70 VAC
Release voltage	30 VAC
Load voltage	24-480 VAC
Load current	60 A
Peak voltage	800 V
Max on-state current drop	2 mA
Input and output insulation voltage	4000 V



I/O terminal to shell insulation voltage

2500 V

Operating temperature

-30°C~80°C

Certification

CE

Terminals

Screw

Dimension

